

March 24, 2009

This addendum is hereby made part of the St. Vincent de Paul of Baltimore- Head Start Southeast Patterson Park and St. Brigid's Site Floor Covering Improvements Scope of Work. Please note the following changes, information and/or instructions and submit your bid accordingly.

**Floor Covering Improvements
Modifications to Scope of Work**

St. Brigid's Site

1. Alternate #1

CHANGE: "Demolish existing VCT in the basement level storage/staff lounge room."
TO READ: "Item deleted from Floor Covering Improvements Scope of Work"

Patterson Park Site

2. Scope of Work

ADD: "**Item #9:** Installation of new vinyl wall base

Location: Rooms: 125, 130, 203, 208

Work: Apply wall base to walls, columns, and other permanent fixtures in rooms or areas where base is required. Install base in lengths as long as practicable, with preformed corner units or fabricated from base materials with mitered or coped inside corners. Tightly bond the base to the substrate throughout the length of each piece with continuous contact at horizontal and vertical surfaces. On masonry surfaces or other similar substrates fill voids along top edge of resilient wall base with manufacturer's recommended adhesive filler material. After installation is complete, remove any excess adhesive or other surface blemishes."