

March 24, 2009

This addendum is hereby made part of the St. Vincent de Paul of Baltimore- Head Start Southeast Patterson Park and St. Brigid's Site Miscellaneous Renovations & Improvements Scope of Work. Please note the following changes, information and/or instructions and submit your bid accordingly.

Miscellaneous Renovations & Improvements
Modifications to Scope of Work

Patterson Park Site

1. Item #1

CHANGE: "Replace (3) damaged ceiling tiles as directed and replace them with new acoustic 2x4 lay-in ceiling tiles to match existing."

TO READ: "Replace (4) damaged ceiling tiles as directed and replace them with new acoustic 2x4 lay-in ceiling tiles to match existing."

2. Item #3

CHANGE: "Replace existing metal panel patches over areas of missing ceiling tiles with new 12x12 ceiling tiles.

Location: Rooms: 118, 127"

TO READ: "Item deleted from Miscellaneous Renovations & Improvements Scope of Work and incorporated elsewhere"

3. Item #4

CHANGE: "Install new hardware set:

- (3) high frequency hinges
- Closer
- Passage function lockset"

TO READ: "Replace hardware set as necessary. Hardware set should include:

- (3) high frequency hinges
- Closer
- Passage function lockset
- Push/pull bar"

4. Item #5

CHANGE: "Replace existing horizontal blinds with new commercial grade blinds.

Location: Rooms: 122"

TO READ: "Item deleted from Miscellaneous Renovations & Improvements Scope of Work."

5. Item #9

CHANGE: "Replace existing residential light fixtures with new fluorescent light fixtures."

TO READ: "Replace (8) existing residential light fixtures with (9) new 1x4 fluorescent light fixtures."

6. Item #14

CHANGE: "Sand and reseal existing exterior wood stairs and ramp."

TO READ: "Item deleted from Miscellaneous Renovations & Improvements Scope of Work"

7. Item #16

CHANGE: "Infill areas of missing or damaged 12x12 ceiling tiles with new tongue and groove ceiling tiles to match the existing"

TO READ: "Infill areas of missing or severely damaged 12x12 ceiling tiles, and areas where metal panel patches have been used to cover areas of missing tiles with new tongue and groove ceiling tiles to match the existing. There are approximately (150) ceiling tiles to replace throughout the site."

8. Scope of Work

ADD: Item #17:

Cut and cap existing water lines.

Location: Rooms: 203, 208